



March 10, 2016

Village of Homer Glen
 14933 S. Founders Crossing
 Homer Glen, IL 60491

Thank you for giving TeamLogic IT the opportunity to bid your project. We look forward to assisting The Village of Homer Glen with this cabling project as well as look forward to working with you on any more upcoming projects. Please note that the bid below reflects the use of prevailing wages.

QTY	DESCRIPTION	RATE	TOTAL
65	CATEGORY 6 DATA PULL, TERMINATE AT PATCH PANEL AND PLATE WITH CAT 6 GIGAMAX MODULAR JACK (568 B), LABELED, TESTED AND CERTIFIED. ALL LINES RUN THROUGH 1/4" X 20 BRIDLE RINGS WITH BEAM CLAMPS, (70) 7'PATCH CABLE	\$100.00	6500.00
2	CATEGORY 6, 48 PORT PATCH PANEL	\$152.50	\$305.00
1	2 POST VERTICLE RACK	\$250.00	\$250.00
1	VERTICAL LADDER RACEWAY WITH WALL KIT	\$155.00	\$155.00
1	FATCAT R-SHELF -1-U UNIVERSAL EQUIPMENT SHELF, VENTED - 1U HIGH (1.75")	\$33.00	\$33.00
2	VERTICAL 45U WIRE MANAGEMENT	\$185.00	\$370.00
8	INSTALL AND MOUNT RACK, LADDER AND WIRE MANAGEMENT SYSTEM SORT, PUNCH DOWN (2) PORT PATCH PANELS	\$60.00	\$480.00
2	6" WALL RACEWAY	\$83.00	\$166.00
2	3" HINGED FROM DUCT COVER 2U WITH RINGS	\$300.00	\$600.00
		TOTAL	\$8,859.00

If you have any questions regarding this proposal please contact me.
 Sincerely,
 Laurie Breese

15774 S. LaGrange Road
 Orland Park, IL 60462
 708.942.4266
www.TeamLogicIT.com/OrlandParkIL.com